

**AACE**  
*September 13*



**SOUNDTRANSIT**  
RIDE THE WAVE



# Today's Presentation

- Overview of Sound Transit and East Link Project
- Work to date
- Challenges
- Track Bridge System




# Sound Transit District



# Sound Transit Program

- **Transit Investments (to date):**
  - 24 express bus projects completed
  - 75 miles of commuter rail service
  - 17.1 miles of light rail service
- **Additional Investments (2023)**
  - 17% express bus service increase
  - 8.2 miles of commuter rail service
  - 36 miles of light rail service






# Extending the regional light rail system




# I-90 bridge lane configuration

## Existing I-90 floating bridge lane configuration


Afternoon Peak Period




## At completion of I-90 Two-Way Transit Project



## At completion of East Link




# East Link Alignment





# I-90 Stations

Rainier Station



Mercer  
Island  
Station




# South Bellevue Station



# Downtown Bellevue and Hospital



East Main  
Station



Hospital  
Station




Bellevue Transit Center  
Station

# Bel-Red Stations




120<sup>th</sup> Station

130<sup>th</sup> Station





# Redmond Stations




Overlake  
Village  
Station

Overlake  
Transit Center  
Station





# East Link Working Schedule





# East Link Status

- Preliminary Engineering complete
- Final EIS published
- FTA and FHWA Records-of-Decision signed
- Final Design
  - Bellevue-Redmond underway
  - I-90 Fall 2012
- Baseline Scope, Schedule, and Budget 2014



# I-90 Independent Review Team (IRT)

- 2008 State Transportation Budget Proviso
  - Up to \$550,000 for an independent technical review, overseen by the Joint Transportation Committee (JTC), of light rail feasibility across the Interstate 90 - Homer Hadley Floating Bridge.
- September 15, 2008 IRT report concluded that:
  - All issues identified as potentially affecting feasibility can be addressed
  - Made recommendations for issues to address during design
- ST and WSDOT are implementing the IRT recommendations

# IRT Classified 23 Issues into 6 Categories

- General
- Stray Current Mitigation Measures
- Impact of LRT Track System Installation on the Bridge
- Seismic Vulnerability of Approach and Transition Spans
- Miscellaneous
- Rail Expansion Joint Design and Prototype Testing



# General

- Criteria Established for Independent Review Team to Evaluate Numerous Issues
- Washington State DOT's and Sound Transit's Goal for the Life Expectancy of Bridge
- Additional Needs and Changes Required for LRT Installation to meet "Blue Ribbon Panel" Recommendations

# Stray Current Mitigation Measures

- Sound Transit Adoption of North Link/Airport Link Stray Current Mitigation Design Criteria for Homer M. Hadley Floating Bridge Installation
- Stray Current and Cathodic Protection System Interference and compatibility
- Determining Strength and Electrical Resistance of Existing Concrete
- Modification of Current Bridge Inspection Procedures for LRT Installation
- Method for Identifying Stray Current Failure and Response/Repair Plan

# Impact of LRT Track System Installation on the Bridge

- Need for Lightning Arrestors on Floating Bridge and Approaches
- Impact of Stray Current Dispersion in Lake Washington on Environment and Fish
- Attachment of OCS Supports to Edge of Homer M. Hadley Floating Bridge Deck Cantilevers
- Methods to be Utilized for Locating Rebar and Post Tensioning in Bridge Deck

# Seismic Vulnerability of Approach Spans and Transition Span

- Seismic Vulnerability and Seismic Retrofit of Approach Spans and Transition Span
- West Approach Tunnel Design Criteria Consistency



# Miscellaneous


- Operational Restrictions for Combination of Train Loading and One - Year Storm Loading from North
- Analysis to Confirm Torsional Capacity of the Existing Bridge
- Analysis of “North Wind” Storm Effects on Homer M. Hadley Floating Bridge
- Operational and Maintenance Coordination Agreement between Sound Transit and Washington State DOT
- Median Barrier Relocation Design, Attachment, Maintenance and Drainage
- Effect of LRT Installation on Construction Operations Associated with Anchor Cable Replacement

# Rail Expansion Joint Design and Prototype Testing

- Track Bridge/Expansion Joint Design and Performance Criteria
- Rider Comfort Performance for LRT Track Bridge at Expansion Joints
- Storm Water Drainage System Modifications under New LRT Track Bridge at Expansion Joints

# Expert Review and Prototype Design

- “Since the track bridge is unique...design should be accelerated and [a] prototype tested...”



- Prototype design contract awarded in February 2011
- 90% Design in 2012
- Fabrication and testing in 2013

# Expansion Joint Locations






# Existing Expansion Joint



# Range of Motion



# Evaluation Criteria

## Performance

- Operating speed
- Restricted speeds

## System Parameters

- Reliability/ Maintainability/ Inspection ability
- Ease of fabrication

## Life Cycle costs

- Initial costs
- Customer Impact/O&M

# Track Bridge Project Team

- Parsons Brinckerhoff/Balfour Beatty Team selected on:
  - Approach
  - Experience
  - Expertise



# Contracting Approach

## Phase 1A (Completed November 2011)

- Develop Alternatives
- Evaluate Alternatives
- Select one alternative for Phase 1B

## Phase 1B (Now through November 2012)

- Prepare 90% design document
- Develop the testing plan
- Component Testing

## Phase 2 (ST's option)

- Build and test prototype in shop
- Full scale field test of prototype


## Phase 3

- ST's option
- Build actual

# Key Contract Features

- Meets Independent Review Team Recommendations
- Design a prototype
- Develop a testing plan
- Incentive fee for exceeding goals and milestones
- Sound Transit option for awarding future phases
  - Phase 2 build and test the prototype
  - Phase 3 build the final track bridge

# CESURA




# Where are we now?

- Preferred alternative selected
- Working towards 90% design
- UW testing under way
- Full scale testing contract will be considered by ST Board October



# UW Lab






# Friction Pendulum Bearing



# Engineering Challenge

## *Expansion Joints Prototype Testing*

- Test Facility in Colorado
- Initial proposal
  - Replicate all movements of Transition Span in Colorado
  - Ship Sound Transit train to Colorado for testing
- Test joint through all movements; service movement and extreme movement
- Redesign, fabricate, retest, if required





# Testing Program

Lateral acceleration on each axle box

Car body roll


Truck rotation

Wheel forces

Rail movement and stresses

Track bridge stresses

Bearing loads rotations, and displacements






# Questions



# Movements Per WSDOT - Vertical

- Vertical 2.2 degrees



# Movements Per WSDOT - Longitudinal

- Longitudinal – Floating  $\pm 2.05$  feet
- Longitudinal – Approach  $\pm .75$  feet



ELEVATION VIEW

# Movements Per WSDOT - Horizontal

